FLOW RATE TEST RESULTS



Client: Aquaknight Industries Ltd

> 33 Leslie Avenue Sandringham Auckland 1025 New Zealand

Date of Test: 04-Dec-2019

Date of Certificate: 05-10-2020

Certificate Number: FLV 013

Product Details

3100.193 Model Number:

100

Model Name: RD BE80

Outlet Size (mm): 80

Inlet Size (mm):

Description:


Roof Drain Bottom Exit 80mm

Testing Conditions:


PVC flange mounted flush into test plinth (datum)

Clamp Ring and grate installed 100/80 reducer bush installed Discharge to atmosphere

Grate Drawing



Installed Drawing










Flow Characteristic Curve





Flow Rate (L/sec)	Water Head (mmH2O)
0.980	10.2
1.977	18.9
2.971	24.2
3.994	30.7
5.008	35.1
6.002	41.0
7.005	70.7
8.010	134.2
9.024	204.2
10.026	283.2
10.919	363.2





© Flowlab Ltd 2020